



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION
NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
Miami, Florida 33175-2474
T (786) 315-2590 F (786) 315-2599
www.miamidade.gov/building

Amarr Garage Doors dba Entrematic
165 Carriage Court
Winston Salem, NC 27105

SCOPE: This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Model 1000 Amarr 2432 Insulated Steel Sectional Garage Doors up to 9'-2" Wide with Impact Resistant Windows – L.M.I.

APPROVAL DOCUMENT: Drawing No. **IBC-1009-195-15-I**, titled "Model 1000 Amarr 2432", sheets 1 through 4 of 4, dated 12/05/16, prepared by manufacturer, signed and sealed by Thomas L. Shelmerdine, P.E., bearing the Miami-Dade County Product Control Renewal stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, manufacturing address, model number, the positive and negative design pressure rating, indicate impact rated if applicable, installation instruction drawing reference number, approval number (NOA), the applicable test standards, and the statement reading 'Miami-Dade County Product Control Approved' is to be located on the door's side track, bottom angle, or inner surface of a panel.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.


ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **renews NOA No. 20-1015.25** and consists of this page 1 and evidence page E-1, E-2 and E-3, as well as approval document mentioned above.

The submitted documentation was reviewed by **Manuel Perez, P.E.**




10/5/22

NOA No. 22-0914.06
Expiration Date: November 09, 2027
Approval Date: October 13, 2022
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's

A. DRAWINGS

1. Manufacturer's die drawings and sections.
(Submitted under NOA No. 17-0321.04)
2. Drawing No. **IBC-1009-195-15-I**, titled "Model 1000 Amarr 2432", sheets 1 through 4 of 4, dated 12/05/16, prepared by manufacturer, signed and sealed by Thomas L. Shelmerdine, P.E.
(Submitted under NOA No. 17-0321.04)

B. TESTS


1. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
2) Large Missile Impact Test per FBC, TAS 201-94
3) Cyclic Wind Pressure Loading per FBC, TAS 203-94
4) Tensile Test per ASTM E8
5) Forced Entry Resistance Test per FBC, TAS 202-94
along with marked-up drawings and installation diagram of Amarr 9'-2"x 8' 24 ga. exterior/27 ga. interior steel insulated garage door Model 1000, prepared by American Test Lab, Inc., Test Report No. **ATLNC 1017.01-16**, dated 12/13/16 and addendum letter dated 06/19/17, both signed and sealed by David W. Johnson, P.E.
(Submitted under NOA No. 17-0321.04)
2. Test report on Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments per ASTM D1654-08 & Salt Spray (Fog) per ASTM B117-11, prepared by Intertek/ATI, Test Report No. **C5463.01-106-18**, dated 04/03/13, signed and sealed by Joseph A. Reed, P.E.
(Submitted under NOA No. 17-0321.04)

C. CALCULATIONS

1. Anchor calculations prepared by Structural Solutions, P.A., dated 03/02/17, signed and sealed by Thomas L. Shelmerdine, P.E.
(Submitted under NOA No. 17-0321.04)

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)


Manuel Pérez, P.E.
Product Control Examiner
NOA No. 22-0914.06
Expiration Date: November 09, 2027
Approval Date: October 13, 2022

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's (CONTINUED)

E. MATERIAL CERTIFICATIONS


1. UL evaluation report on Surface Burning Characteristics per ASTM E84 and ANSI/UL723 of Grade 54 and 40 Expandable Polystyrene Resins manufactured by Flint Hills Resources, Evaluation Report #**UL ER7503-01**, dated May 22, 2013 and revised on May 12, 2014.
2. UL evaluation report on Potential Heat of Building Materials per NFPA 259-2008 and on Self-Ignition Temperature per ASTM D1929, Project #4786090680.1.1, File R7503, dated 12/20/2013, signed by R.K. Laymon.
3. Notice of Acceptance No. **17-0410.01** issued to **Covestro, LLC** for their "**Makrolon Polycarbonate Sheets**" dated 06/08/17, expiring on 08/27/22.

F. STATEMENTS

1. Statement letter of conformance, complying with **FBC 7th Edition (2020)** and of no financial interest, dated August 27, 2020, issued by Structural Solutions, PA., signed and sealed by Thomas L. Shelmerdine, P.E.
(Submitted under NOA No. 20-1015.25)

G. OTHERS

1. Notice of Acceptance No. **17-1010.21**, issued to Amarr Garage Doors dba Entrematic for their Model 1000 Amarr 2432 Insulated Steel Sectional Garage Door up to 9'-2" Wide with Impact Resistant Windows – L.M.I., approved on 12/21/17 and expiring on 11/09/22.


Manuel Pérez, P.E.
Product Control Examiner
NOA No. 22-0914.06
Expiration Date: November 09, 2027
Approval Date: October 13, 2022

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

2. NEW EVIDENCE SUBMITTED

A. DRAWINGS

1. None.

B. TESTS

1. None.

C. CALCULATIONS

1. None.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS


1. Notice of Acceptance No. **22-0317.02** issued to **Plaskolite, LLC** for their “**TUFFAK Polycarbonate Sheets**” dated 04/21/22, expiring on 08/27/27.



F. STATEMENTS

1. Statement letter of conformance, complying with **FBC 7th Edition (2020)** and of no financial interest, dated August 23, 2022, issued by Structural Solutions, P.A., signed and sealed by Thomas L. Shelmerdine, P.E.

G. OTHERS


1. Notice of Acceptance No. **20-1015.25**, issued to Amarr Garage Doors dba Entrematic for their Model 1000 Amarr 2432 Insulated Steel Sectional Garage Door up to 9’-2” Wide with Impact Resistant Windows – L.M.I., approved on 01/21/21 and expiring on 11/09/22.


Manuel Pérez, P.E.
Product Control Examiner
NOA No. 22-0914.06
Expiration Date: November 09, 2027
Approval Date: October 13, 2022




DOOR INTERIOR ELEVATION
N.T.S.


PRODUCT RENEWED
as complying with the Florida
Building Code
NOA-No. 22-0914.06
Expiration Date: 11/09/2027
By: Manuel Perez
Miami-Dade Product Control



TYPICAL END HINGE
N.T.S.


PRODUCT APPROVED
as complying with the Florida
Building Code
NOA-No. 17-0321.04
Approval Date 11/09/2017
By 
Miami-Dade Product Control

PRODUCT REVISED
as complying with the Florida
Building Code
NOA-No. 20-1015.25
Expiration Date: 11/09/2022
By: Manuel Perez
Miami-Dade Product Control



TYPICAL BOTTOM BRACKET
N.I.S.

PRODUCT REVIEW
as complying with the Florida
Building Code
Acceptance No 17-1010-21
Expiration Date NOV 9, 2022
By Isahang I. Chaudhry
Isahang I. Chaudhry, PE




2" BRACKET MOUNT TO WOOD JAMB DETAIL
N.T.S.

LARGE MISSILE IMPACT RESISTANT

REV	DESCRIPTION OF REVISIONS	DATE	BY
<p>MAX SIZE 8'2 x 24'</p> <p>DESIGN LOADS +55.1 PSF -64.5 PSF</p> <p>TEST LOADS +82.7 PSF -96.8 PSF</p> <p>LARGE MISSILE IMPACT RESISTANCE</p>		<p>Thomas L. Sheldermine, PE (FL PE #0048579) Structural Solutions, PA (FL Firm #29412)</p> <p>FL</p> <p><i>Amarr</i> ENTREMATiC</p> <p>MODEL 1000 AMARR 2432</p>	
SIZE	DRAWN BY	CRD	DATE
B	CHECKED BY	RLR	DATE
<p>ENTREMATiC</p> <p>165 CARRIAGE COURT WINSTON-SALEM, NC 27105</p>		<p>DRAWING NUMBER</p> <p>IBC-1009-195-15-1</p> <p>SHEET 1 OF 4</p>	


TRACK CONNECTION DIRECTLY TO STRUCTURE OPTIONS



CLIP STYLE REVERSE ANGLE MOUNT SHOWN
BRACKET, CONTINUOUS AND TAPERED ANGLE
MOUNT AVAILABLE


12 GA. STEEL FRAMING
232 LBS./SCREW ALLOWABLE LOAD - 6" FROM ENDS
AND 10" O.C.
REFER TO NOTES: 1, 2 AND 5

3/16" STEEL FRAMING
569 LBS./SCREW ALLOWABLE LOAD - 6" FROM ENDS
AND 24" O.C.
REFER TO NOTES: 1, 2 AND 5




REVERSE ANGLE MOUNT SHOWN
BRACKET, CONTINUOUS AND TAPERED
ANGLE MOUNT AVAILABLE

STEEL FRAMING 12GA OR BETTER
1590 LBS./IN. ALLOWABLE LOAD - 6"
FROM ENDS AND 24" O.C.
REFER TO NOTES: 1, 2, 5, 6, 7, 8 AND 9



CLIP STYLE CONTINUOUS ANGLE MOUNT SHOWN
BRACKET, REVERSE AND TAPERED ANGLE MOUNT
AVAILABLE

2000 PSI CONCRETE OR GREATER
351 LBS./EXPANSION ANCHOR ALLOWABLE LOAD - 6"
FROM ENDS AND 16" O.C.
REFER TO NOTES: 1, 2, 3, 4 AND 5



CONTINUOUS ANGLE MOUNT SHOWN
BRACKET, CONTINUOUS AND TAPERED ANGLE
MOUNT AVAILABLE

2000 PSI CONCRETE OR GREATER
936 LBS./EXPANSION ANCHOR ALLOWABLE LOAD - 6"
FROM ENDS AND 16" O.C.
REFER TO NOTES: 1, 2, 3, 4 AND 5

WOOD JAMB ATTACHMENT TO STRUCTURE (OPTIONAL)

2 X 6 VERTICAL JAMB ATTACHMENT TO WOOD FRAME STRUCTURE
5/16" X 3" LAG SCREWS STARTING 6" FROM ENDS
THEN 18" O.C. (1 1/2" EMBEDMENT)

2 X 6 VERTICAL JAMB ATTACHMENT TO 2,000 PSI CONCRETE
HILTI KWIK BOLT 3/8" X 4" STARTING 6" FROM ENDS
THEN 24" O.C. (2 1/2" EMBEDMENT)


HILTI SLEEVE ANCHOR 3/8" X 2-3/4" STARTING 6" FROM ENDS
THEN 16" O.C. (1 1/4" EMBEDMENT)
ITW/RAMSET REDHEAD (TRU-BOLT) 3/8" X 4" STARTING 6" FROM ENDS
THEN 24" O.C. (2 1/2" EMBEDMENT)

2 X 6 VERTICAL JAMB ATTACHMENT TO HOLLOW C-90 BLOCK
SIMPSON 1/4" X 3" TITEN SCREWS STARTING 6" FROM ENDS,
USE PAIRS OF FASTENERS (3" APART)
AT 8" O.C. (1 1/2" EMBEDMENT)

HILTI 1/4" X 2-3/4" KWIK-CON II+ SCREWS STARTING 6" FROM ENDS,
USE PAIRS OF FASTENERS (3" APART) AT 8" O.C. (1 1/4" EMBEDMENT)

2 X 6 VERTICAL JAMB ATTACHMENT TO GROUTED C-90 BLOCK (2000 PSI GROUT)
HILTI SLEEVE ANCHOR 3/8" X 2-3/4" STARTING 6" FROM ENDS
THEN 20" O.C. (1 1/4" EMBEDMENT)
(OR, USE FASTENERS FOR HOLLOW C-90 BLOCK)

*LAGS AND BOLTS CAN BE COUNTERSUNK TO PROVIDE A FLUSH MOUNTING SURFACE.
*PREPARATION OF WOOD JAMBS BY OTHERS



PRODUCT REVISED
as complying with the Florida
Building Code

NOA-No. **20-1015.25**

Expiration Date: **11/09/2022**

By: *Manuel Perez*
Miami-Dade Product Control

PRODUCT RENEWED
as complying with the Florida
Building Code

NOA-No. **22-0914.06**

Expiration Date: **11/09/2027**

By: *Manuel Perez*
Miami-Dade Product Control

NOTES:

1. ANCHORS TO BE EVENLY SPACED BETWEEN THE HEADER AND FLOOR.
2. FIRST (BOTTOM) ANCHOR STARTING AT NO MORE THAN HALF OF THE MAXIMUM ON-CENTER DISTANCE, HIGHEST ANCHOR INSTALLED AT LEAST AS HIGH AS THE DOOR OPENING.
3. MIN. EDGE DISTANCE OF 3" REQUIRED.
4. USE WASHERS PROVIDED BY THE ANCHOR MANUFACTURER.
5. SUPPORTING STRUCTURAL ELEMENTS SHALL BE DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER FOR WIND LOADS IN ADDITION TO OTHER LOADS.
6. MOST GARAGE DOOR TRACK IS GALVANIZED STEEL. USE ALL NECESSARY PRECAUTIONS WHEN WELDING GALVANIZED STEEL.
7. ALL WELDS SHOULD BE PERFORMED BY A CERTIFIED WELDER OR INSPECTED BY A CERTIFIED WELDING INSPECTOR TO VERIFY THE INTEGRITY OF THE WELD.
8. FILLET WELDS TO HAVE A STRAIGHT OR CONVEX FACE SURFACE.
9. TACK WELD TOE OF ANGLE AT SAME SPACING TO PREVENT ROTATION OF TRACK ANGLE.


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. **17-1010.21**
Expiration Date: **11/9/22**
Ismael L. Chaves
Miami-Dade Product Control

PRODUCT APPROVED
as complying with the Florida
Building Code
NOA-No. **17-0321.04**

Approval Date: **11/09/2017**

By: *Thomas L. Shelmerdine*
Miami-Dade Product Control

REV	DESCRIPTION OF REVISIONS	DATE	BY
	MAX SIZE 9'2" x 24'		
	DESIGN LOADS +55.1 PSF -64.5 PSF		
	TEST LOADS +82.7 PSF -96.8 PSF		
	LARGE MISSILE IMPACT RESISTANCE		
	Thomas L. Shelmerdine, PE (FL PE #0048579) Structural Solutions, PA (FL Firm #29412)		



Thomas L. Shelmerdine, PE (FL PE #0048579)
Structural Solutions, PA (FL Firm #29412)
5921-G W. Friendly Ave., Greensboro, NC 27410

Amarr
ENTREMATICS


MODEL 1000 AMARR 2432



SIZE	DRAWN BY	DRD	DATE	11/16/16	DRAWING NUMBER
B	CHECKED BY	RLR	DATE	12/05/16	IBC-1009-195-15-1
					ENTREMATICS
					165 CARRIAGE COURT WINSTON-SALEM, N.C. 27105

SHEET 2 OF 4

TRACK CONNECTION TO WOOD JAMB OPTIONS


FOR LAG SCREWS & BRACKET SPACING SEE PAGE 3 FOR TRACK CONFIGURATION DETAIL






SPECIFICATIONS AND NOTES

1. ALL THE LOAD FROM THE DOOR IS TRANSFERRED TO THE VERTICAL TRACK, FROM THE TRACK THE LOAD IS TRANSFERRED TO THE VERTICAL JAMBS. THE HORIZONTAL JAMB OR HEADER RECEIVES NO PORTION OF THE LOAD TRANSFERRED FROM THE DOOR.
2. EACH VERTICAL JAMBS RECEIVES MAXIMUM DESIGN LOADS OF:
+252.6 LBS/FT & -295.6 LBS/FT
3. DOOR AND HARDWARE WILL BE DESIGNED, MANUFACTURED AND INSTALLED WITH STANDARDS AS SET FORTH BY DASMA.
4. DOOR SECTIONS SHALL BE 24 GA. (.021) MIN. EXTERIOR SKIN ROLLED FORMED, G30 GALVANIZED W/ POLYESTER TOP COAT
5. DOORS UP TO 24'0" HIGH HAVE (2) 3" 20GA STRUTS PER SECTION
6. SUPPORTING STRUCTURAL ELEMENTS SHALL BE DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER FOR WIND LOADS INDICATED ON THIS DRAWING IN ADDITION TO OTHER LOADINGS.
7. THIS APPROVAL REQUIRES THE MANUFACTURER TO DO TESTING OF ALL COILS USED TO FABRICATE DOOR PANELS UNDER THIS NOTICE OF ACCEPTANCE. A MINIMUM OF 2 SPECIMENS SHALL BE CUT FROM EACH COIL AND TENSILE TESTED ACCORDING TO ASTM E-8 BY A DADE APPROVED LAB SELECTED AND BY THE MANUFACTURER. EVERY 3 MONTHS, 4 TIMES A YEAR, THE MANUFACTURER SHALL MAIL TO THIS OFFICE: A COPY OF THE TEST REPORTS WITH CONFIRMATION THAT THE SPECIMENS WERE SELECTED FROM COILS AT THE MANUFACTURER PRODUCTION FACILITIES. AND A NOTARIZED STATEMENT FROM THE MANUFACTURER THAT ONLY COILS WITH YIELD STRENGTH OF 49,000 PSI OR MORE SHALL BE USED TO MAKE DOOR PANELS FOR DADE COUNTY UNDER THIS NOTICE OF ACCEPTANCE.



OPTIONAL GLAZED SECTION W/LONG PANEL IMPACT WINDOWS
N.T.S.



OPTIONAL GLAZED SECTION W/LONG PANEL IMPACT WINDOWS
N.T.S.



PRODUCT RENEWED
as complying with the Florida
Building Code

NOA-No. 22-0914.06

Expiration Date: 11/09/2027

By: Manuel Perez

Miami-Dade Product Control

PRODUCT REVISED
to comply with the Florida
Building Code

7 **Tracking Code**
 17-1010-2

Acceptance No 17-1810-2
Expiration Date 11/9/12

14001 (14001)

Shang, L. H. H.

PRODUCT REVISED
as complying with the Florida
Building Code

NOA-No. 20-1015.25

Expiration Date: 11/09/2022

By: Manuel Perez

Miami-Dade Product Control

PRODUCT APPROVED
as complying with the Florida
Building Code

NOA-No. 17-0321.04

Approval Date 11/09/2017

By [Signature]
Miami-Dade Product Control

REV	DESCRIPTION OF REVISIONS	DATE	BY

<p>MAX SIZE 9'2" x 24'</p> <p>DESIGN LOADS +55.1 PSF -64.5 PSF</p> <p>TEST LOADS +82.7 PSF -96.8 PSF</p> <p>LARGE MISSILE IMPACT RESISTANCE</p>	<p>Thomas L. Shelmerdine, PE (FL PE #0048579) Structural Solutions, PA (FL Firm #29432)</p> <p>FL</p>		<p>dbe Structural Solutions of North Carolina, Inc.</p>
---	---	--	---

ENTREMAT^{IC}

MODEL 1000 AMARR 2432

SIZE B	DRAWN BY RDR	DATE 11/16/16	DRAWING NUMBER IBC-1009-195-15
CHECKED BY RLR	DATE 12/05/16	SHEET 3 OF 4	

ENTREMAT^{IC}

165 CARRIAGE COURT WINSTON-SALEM, N.C. 27105

DOOR HEIGHT	TRACK ATTACHMENT																							
	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	
7' 0"	3.5"	10.0"	22.0"	34"	46"	58"																		
7' 6"	3.5"	10.0"	22.0"	34"	46"	58"	70"																	
8' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"																	
8' 6"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"																
9' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"																
9' 6"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"															
10' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"															
11' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"														
12' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"													
13' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"												
14' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"											
15' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"										
16' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"									
17' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"	178"								
18' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"	178"	190"							
19' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"	178"	190"	202"						
20' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"	178"	190"	202"	214"					
21' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"	178"	190"	202"	214"	226"				
22' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"	178"	190"	202"	214"	226"	238"			
23' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"	178"	190"	202"	214"	226"	238"	250"		
24' 0"	3.5"	10.0"	22.0"	34"	46"	58"	70"	82"	94"	106"	118"	130"	142"	154"	166"	178"	190"	202"	214"	226"	238"	250"	262"	

DOOR HEIGHT

VERTICAL LIFT

HIGH LIFT



STANDARD LIFT

LOW HEADROOM

SPlice TRACKS w/ (4)-20 TRACK SPlice BOLTS & NUTS

2" (.083 MIN.) OR 3" (12 GA. MIN.) VERTICAL TRACK

AVAILABLE TRACK CONFIGURATIONS
N.T.S.

REV	DESCRIPTION OF REVISIONS	DATE	BY
<p>MAX SIZE 9'2 x 24'</p> <p>DESIGN LOADS +55.1 PSF -64.5 PSF</p> <p>TEST LOADS +82.7 PSF -96.8 PSF</p> <p>LARGE MISSILE IMPACT RESISTANCE</p>	<p>Thomas L. Shelmerdine, PE (FL PE #0048579) Structural Solutions, PA (FL Firm #29412)</p> <p>FL</p>  <p>dbb Structural Solutions of North Carolina, Inc. 5921-G W. Friendly Ave., Greensboro, NC 27410</p>		
MODEL 1000 AMARR 2432			
SIZE B	DRAWN BY DRD	DATE 11/15/16	DRAWING NUMBER IBC-1009-195-15-1
CHECKED BY RLR	DATE 12/05/16	SHEET 4 OF 4	
ENTREMATiC 165 CARRIAGE COURT WINSTON-SALEM, N.C. 27105			