# SBD CM REVIEW FORM

**To**: Project Review and Analysis Division - Construction
**From:** SBD CM - Ileana Quintana
**Department:** Water & Sewer Department **Contact:** Jose Vilaboy
**Date:** 12 / 05 / 2011

**PROJECT NUMBER:** RPQ P0075 (Formerly RPQ P0054)
**PROJECT TITLE:** P.S. 348 Odor Control and Wet Well Corrosion Rehabilitation
**PROJECT LOCATION:** 5700 E 8 Avenue, Hialeah Florida 33013

**SCOPE OF WORK/DESCRIPTION:** Consists of furnishing all labor, material and equipment; furnishing and installing new odor control system with two 60"x80" scrubbers in series with a fan; material for rehabilitation of existing Wet Well with a concrete protecting coating to include inlet channels, stairs, platform, walls and roof slab; providing 24 hour manned by-pass pumping with primary and back up pumps for a regional pump station; furnishing and installing 14" and 12" diameter PVC pipe and fitting s for odor control system; furnishing and installing electric conduits, wiring and all other electrical materials; furnishing and installing handrail for stair at existing wet well; demolishing of existing odor control system, odor control building, exhaust piping and appurtenant items; removing of all sod, soil and roofing cover above all the existing wet well slab; furnishing and placing light weight concrete over wet well slab; removing existing sluice gate at wet well influent line; replacement of any sod, sidewalk and pavement damaged during construction.

**SPECIAL REQUIREMENTS:** The Contractor shall have established, operated and maintained at least three successful by-pass pumping operations; shall have had primary responsibly for the by-pass operation and the operation shall have been completed successfully without spills or overflow.

| TRADES | AMOUNT | COMMENTS |
|---|---|---|
| | | General Engineering / General Contractor |
| Mobilization | $28,000 | Prime |
| Site preparation *(General Engineering Contractor/Pipeline Contractor)* | $30,000 | Possible subcontracting opportunity |
| Demolition *(Demolition Contractor)* | $40,000 | |
| Wet well rehabilitation | $314,000 | Primary scope of work includes all line items noted |
| Electrical | $110,000 | |
| Temporary by-pass | $172,000 | |
| | | |
| Estimated Total Construction Cost | $694,000 | |
| | | |
| | | |
| Dedicated | $30,000 | |
| Permit fee | $34,700 | |
| Contingency | $69,400 | |
| | | |
| | | |
| Total Estimated Construction Cost | $828,100 | |
| | | |

Small Business Development Signature:_____ Date: 12 / 07 / 2011

*** Trades/Subtrades identified for possible subcontracting opportunities identified by SBD CM**

- WASD is recommending No Measure.