

SBD – CM REVIEW FORM

To: Business Opportunity Support Division – Construction
From: SBD CM Vivian Forhat-Diaz
Company: HUNT – Miami Dolphin Stadium **Contact:** Marsha Jackman
Date: 09/09/2014 **RESUBMITTAL:** No

PROJECT NUMBER: BP- 4 (A & B)
PROJECT TITLE: Vertical Transportation for Miami Dolphins Stadium Renovation
PROJECT LOCATION: Miami Dolphins Stadium

SCOPE OF WORK/DESCRIPTION: For Elevators (BP-04a): Subcontractor shall provide “Machine Room Less” Elevator Modernization of elevators A1, E2 (passenger) and E3 (freight), including but not limited to machine room equipment, controllers, hoist way equipment, traveling cable, hoist way entrances, sill angles, hoist-way and machine room access panels, car equipment, car enclosures, car platforms, car entrances, finishes, hall control stations, signals & control and display panels and all other required items as indicated by the Contract Documents for a complete and approved operating system. Subcontractor shall provide a Group Control and Display system for all elevator cars in the facility, including but not limited to Control Panel, Firefighters’ Control Panel, Firefighters’ Key Box, Machine room Display units, Machine room monitoring system, Visual Displays, etc. Subcontractor shall provide a Monitoring System including but not limited to monitoring displays, monitoring equipment, network & monitoring requirements, reporting requirements, interface to third party building management systems, etc. Subcontractor shall provide a Intercom and Distress Signal System including but not limited to Basic equipment, station housings, etc.

Scope of Work for Escalators 1 thru 8 (BP-04b): Subcontractor shall provide all escalators including but not limited to the steel, stainless and aluminum materials, support trusses, machine room equipment, wellway equipment, handrails, balustrades, landings, signal and control fixtures, signs, stainless steel cladding, all operating hardware, motors, tracks, driving machine, brakes, controller sprocket assemblies, chain, steps, control station, handrail drive, guides, handrails, plates, galvanized drip pans, safety devices, signage, controls and control wiring, conduit, and all other items and accessories required and necessary for a complete operating system. All escalators shall be Heavy Duty, High-Traffic escalators and fabricated for exterior conditions. Subcontractor shall provide all required conduit and wire to make the final power connection to the main disconnect switch by others. Subcontractor shall provide all fire alarm recall, fire fighters’ service, security, telecommunications/intercom and other indicated specialty systems equipment and wire for escalators, as indicated by the Contract Documents.

SPECIAL REQUIREMENTS: None.

TRADES/SUBTRADES	AMOUNT	COMMENTS
		PRIME
Procure and install all Vertical transportation (Elevators & Escalators) as required per the Contract Documents.	\$4,000,000.00	Company procuring the Vertical Transportation will perform the installation. No ancillary work that can be sub-contracted.
Total Cost	\$4,000,000.00	

Small Business Development Signature: Vivian Forhat-Diaz Date: 09/16/14

*Trades/Subtrades identified for possible subcontracting opportunities by SBD CM