



# Small Business Development Division

## Project Worksheet

Project/Contract Title: Hurricane Irma - Charles Deering Estate - Peoples Dock Reconstruction Received Date: 8/27/2020  
 Project/Contract No: HI 50250118004 Funding Source: Federal  
 Department: Parks, Recreation and Open Spaces  
 Estimated Cost of Project/Bid: \$244,145.00

Description of Project/Bid: Removal of the submerged gangway, floating dock, and timber deck system and railing from the existing wood dock: •Installation of a 12 foot wide by 20 foot long (240 square feet) floating dock with aluminum grating located at the east end of the aluminum gangway between 16.3 and 28.3 feet water ward of the main concrete dock. The floating dock will be secured by 4 existing concrete piles. •Installation of a 6 foot wide by 30.5 foot long (183 square foot) aluminum gangway located on the east side of the existing wood pier between 16.3 and 22.3 feet water ward of the main concrete dock. The aluminum gangway will be supported by wood pier and the floating dock. •Installation of a 3.5 foot wide by 6 foot long gangway toe plate centered on the floating dock at the water ward edge of the aluminum gangway. •Installation of permanent railing a minimum of 3 feet high along the perimeter of the wood pier and floating dock.

Contract Measures Recommendation		
Measure	Program	Goal Percent
No Measure	SBE - Con	
Reasons for Recommendation		
<b>SMALL BUSINESS ENTERPRISE - CONSTRUCTION (SBE-Con)</b>		
An analysis of the factors contained in the project package, as well as the factors contained in Implementing Order 3-22 indicates a No Measure is appropriate for this contract due to the Funding Source (Federal Funds).		
CWP Not Applicable: Funding Source		
NAICS 237990 Other Heavy and Civil Engineering Construction, NAICS 236220 Commercial and Institutional Building Construction		

Living Wages: YES  NO  Highway: YES  NO  Heavy Construction: YES  NO   
 Responsible Wages: YES  NO  Building: YES  NO

  
 \_\_\_\_\_  
 SBD Director

8/31/20  
 \_\_\_\_\_  
 Date