


**Date:** March 23, 2021

**To:** Gary T. Hartfield, Division Director  
Small Business Development Division  
Internal Services Department

**From:** Alfredo E. Munoz, P.E.   
Chief, Capital Improvements Division  
Department of Transportation and Public Works

**Subject:** Notice of Construction Project:  
Miscellaneous Construction Contracts: MCC 7360  
Plan CICC 7360-0/08 - Request for Price  
Quotation (RPQ) No.20210057  
Roadway Resurfacing – Multiple Sites

---

**RECOMMENDATION**

The Department’s Capital Improvements staff completed the review of the subject RPQ in accordance with the applicable provisions of Implementing Order 3-22 and recommends a Small Business Enterprise - Construction (SBE-CONST) measure. A Community Workforce Program (CWP) goal, if applicable, is to be determined by Small Business Development.

Scope of Work:	Multiple Trade – Roadway Improvements – Multiple Sites
Engineer Project Base Cost Estimate	
Including Contingency:	\$3,329,135.76
SBE-CONST Measure:	Trade Set Aside
SBE-GS Measure:	Not Applicable
CWP:	As Applicable

**SCOPE OF WORK**

Work under this Contract includes furnishing of all supervision, labor, materials, tools, equipment and performing all operations required to construct the Work in accordance with the Contract Documents.

Work includes but is not limited to the following: Milling and resurfacing, widening and resurfacing of intersecting streets, up to the existing joint at the side street or up to the point of curvature as determined by the Engineer or as indicated in the Plans, resurfacing of asphaltic pathways (pedestrian, bicycle, etc.) adjacent or not to the edge of pavement as necessary, temporary utility repairs (cold patches), clearing and excavating of shoulder areas or build-up, as directed by the Engineer; grading and clean-up of adjacent shoulders and removal of roots, as required, pavement markings including the installation of reflective pavement markers (blue/blue) at fire hydrant locations, sidewalk, sidewalk curbs and connectors, and pedestrian ramps. The Engineer will make the final determination of any changes required due to conflict of design and or field conditions.

Resurfacing work may include any of the following:

1. Application of asphaltic concrete surface course to existing wearing course.

2. Application of asphaltic concrete leveling courses to existing wearing surfaces prior to and in preparation for item 1 above.
3. Application of asphaltic concrete to previously primed rock roads.
4. Fathering of the asphaltic concrete mat on private driveways to a point two (2) feet from the edge of the roadway. Resurfacing of the remainder of private driveways is expressly prohibited under this Contract, unless directed by the Engineer.
5. Adjustment of all storm water, water and sewer valves and manholes prior to resurfacing. All adjustments shall be made by the built-up method, not by the use of adjustment of rings.

Should you require any additional information, please call me at (305) 375-4891, or Alicia Arce at (305) 375-1363.

Attachments (2)

AM/aa

cc: Laurie Johnson, ISD/SBD  
Jhonnatan Escalante, ISD  
Marcia Martin, ISD  
Daniel Viaud, DTPW  
Project File

Alicia Arce, DTPW  
Roxana Bayarre, P.E., DTPW  
Rene Idarraga, P.E., DTPW  
Joaquin Rabassa, P.E., DTPW