

## JBT Box Installation

**RFI Line Items**

ECPU:ESTIMATED COST P/UNIT

PMP:POTENTIAL MINIMUM PURCHASE

PAP:POTENTIAL ANNUAL PURCHASE

PF:PURCHASE FREQUENCY

ETD:ESTIMATED DELIVERY TIME

Product name	MFR	MFR product #	ECPU	Min qty	PMP	PAP	PF	ETD	Details
Cables	BELDEN	1818R / 8233a / 2804RW / B96570		1			1	2	3000ft- (4ea 750ft runs), Belden 1818R Audio Snake Cable, 12 Pair 22AWG, PP Insulation, Individually Foil Shielded and PVC Jacketed, Overall Beldfoil® Shield, PVC Jacket. 1500ft- (2ea 750ft runs), Belden 8233a Video Triax, RG-11 riser rated, 14AWG Solid BC, Double Copper Braids, Overall PVC Jkt. 1500ft- (2ea 750ft runs), Belden 2804RW - Indoor/Outdoor Stadium Cable, SMPTE 311M, 2 Fiber, 2 Conductor 24 AWG, 4 Conductor 20 AWG, CPE Jacket 1500ft- (2ea 750ft runs), Belden B96570 - Tactical Cable OS2 12 Fiber, with Black Jacket Includes shipping
Custom Fabricated/Engraved Connection Panels				1			1	2	(10) Custom punched 19" Rackmount panels, Black with white engraved lettering for (2) JBT Box locations 545 a/b (6) 1.75" Standard 19" rackmount black blank panel dividers. (84) Middle Atlantic Black Rack Screws. (5) Custom punched 19" Rackmount panels, Black with white engraved lettering for Truck Bay I/O rack connection field Includes shipping
Labor to install cabling				1			1	1	Labor to install cabling from Truck Bay computer floor into cable tray and up to Main Concourse telecom room, pull thru conduit pathways to mounted JBT boxes
Labor to perform cable termination				1			1	1	Labor to terminate cable, Audio, Triax, SMPTE fiber and ST-Fiber with fusion splicing method.
Labor to test/tone-out all connections for final acceptance.				1			1	1	Labor to test/tone-out all connections for final acceptance
Totals									