

Data Center Fiber - Conduits

RFI Line Items

ECPU:ESTIMATED COST P/UNIT

PMP:POTENTIAL MINIMUM PURCHASE

PAP:POTENTIAL ANNUAL PURCHASE

PF:PURCHASE FREQUENCY

ETD:ESTIMATED DELIVERY TIME

Product name	MFR	MFR product #	ECPU	Min qty	PMP	PAP	PF	ETD	Details
INSTALL (4) 4" EMPTY CONDUITS				1			1	5	TO PROVIDE AND INSTALL (4) 4" EMPTY CONDUITS FROM CENTER OF DATA CENTER TO BUILDING SHAFT TO SERVE AS A COMMUNICATION RACEWAY BETWEEN BUILDING SHAFT AND NEW DATA CENTER ROOM ON NORTH SIDE AND ON SOUTH SIDE PROVIDE AND INSTALL ALL REQUIRED NEMA PULLBOXES WITH PULL STRING FROM CENTER OF DATA CENTER TO NORTH SHAFT (4) 4" EMPTY CONDUITS WITH PULL STRING FROM CENTER OF DATA CENTER TO SOUTH SHAFT (4) 4" EMPTY CONDUITS WITH PULL STRING EXCLUSIONS: INSTALLATION OF FIBER OPTICS, LOW VOLTAGE WIRING, WORK INSIDE NEW DATA CENTER TOTAL COST INCLUDING LABOR AND MATERIALS USING FACILITY LIFTS WHERE AND IF APPLICABLE
Totals									