

Northeast Area Paver Replacement

RFI Line Items

ECPU:ESTIMATED COST P/UNIT

PMP:POTENTIAL MINIMUM PURCHASE

PAP:POTENTIAL ANNUAL PURCHASE

PF:PURCHASE FREQUENCY

ETD:ESTIMATED DELIVERY TIME

Product name	MFR	MFR product #	ECPU	Min qty	PMP	PAP	PF	ETD	Details
Northeast Area Paver Replacement				1			1	20	End-of-life paver removal and replacement along northeast area of the building. Service to include: • Removal of approximately 5,500 square feet of existing 1" concrete pavers. • Disposal and/or recycling (preferred method) of removed concrete pavers. • Supply and install approximately 5,500 square feet of new 2-3/8" thick white/gray blend brick pavers. • Perform minor repairs as needed. • Chemically clean and seal newly installed pavers with Sika Grout 50lb. High Performance Grout. • Contractor will be responsible for all site preparation (i.e. safety precautions, barricades, cones, site cleaning, materials organization). • Contractor will be responsible for coordination, scheduling and delivery pavers from manufacturer.
Totals									