Welcome!







THE UNDERLINE PHASE 3

PUBLIC MEETING CYCLE #3- OCTOBER 10 AND 11, 2023

PRESENTED BY

MIAMI-DADE COUNTY DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS (DTPW)

Agenda

Meeting Guidelines

Introductions

Design and Construction Presentation

Q&A Session

Final Design Display



Guidelines

In an effort to maintain a safe and respectable forum, we ask that participants abide by the following guideines during the designated Q&A portion.

- Use an index card to write down your question.
- Pass it to a volunteer
- Questions and comments will be selected for discussion after the presentation.



Welcome

Meg Daly

Founder / CEO Friends of The Underline



Welcome

Irene Hegedus

Chief of Transportation Enhancements + Special Projects
Miami-Dade County Department of Transportation and Public Works



Design-Build Joint Venture

























Design and Engineering Team



The Underline is transforming the land below Miami's Metrorail into a 10-mile linear park, urban trail, and public art destination.

3 key priorities for The Underline:

- safe multi-modal transportation
- nature
- community



Safety: dedicated biking and walking paths, lighting and improved crosswalks.





Nature: native vegetation inspired in local plant communities of South Florida.



Community: connecting people to their environment and each other.

Why are we here?





The Underline Phase 3: the seven segments will be built in two stages



The Underline Phase 3: the first construction stage will include Segments 3, 5 and 9

Three public meeting cycles total:

- 1: listening (completed in December, 2022)
- 2: initial ideas (completed in May / June 2023)
- 3: final design & construction information for segments 3, 5 and 9 (today!)



Three public meetings where held in December 2022.





Three public meetings where held in May / June 2023.


What you told us about Phase 3.

Key themes for The Underline phase 3:

- a naturalized, urban corridor
- activated with interactive art & cultural events
- including areas for fitness & sports
- with food experiences
- prioritizing safety



Paths & Intersections: dedicated bike and one pedestrian paths with 25 improved intersections



ADJACENT ROADWAY DEDICATED OFF-ROAD TWO-WAY BICYCLE PATH W/ PAVED SHOULDERS DEDICATED PED PATH W/ PAVED SHOULDERS


ADJACENCY VARIES (ROADWAY, COMMERCIAL OR RESIDENTIAL)




Bike Path: one dedicated, two way, 10-foot wide bike path with a min. 5-foot planted area along US-1




Pedestrian Path: one dedicated, 8-foot wide pedestrian path with seating areas




Intersections: SW22nd Avenue proposed improvements




The Underline Phase 3: 12 new, community spaces






























The Underline Phase 3: the first construction stage will include four community spaces

A- GROVE GALLERY B- THE UNDERLINE PLAZA






C- BARK PARK



L- BUTTERFLY GARDENS





Phase 1 Brickell Backyard- Before

Phase 1 Brickell Backyard- After

Planting: creating a new urban ecological corridor


The Underline phase 3 primary planting goals include:

- preservation of existing & healthy canopy+ addition of new canopy
- re-introduction of native plant communities
- improve site resilience with bioretention & rain gardens
- support ecological functions with new habitats

When complete, The Underline phase 3 will include 3,960 trees and palms!

```
    → 1,688 to remain in place
    → 472 to be relocated on site
    → 1,800 new trees and palms
```

Increasing trees and palms by 62.5%!



Planting: Two strategies for the creation a new urban ecological corridor


Segment 9 Tree Management & Planting Strategy



Segment 9: from Dadeland South Station to SW 80th St.

EXISTING CONDITION

349 TREES



PROPOSED CONDITION

543 TREES (56% INCREASE)

264 TREES TO REMAIN

264 TREES TO REMAIN

• 76 TREES TO BE RELOCATED




•76 RELOCATED TREES

• 9 TREES TO BE REMOVED

No specimen trees will be removed.

2 are dead, prohibited or in poor health.

7 are in conflict with design elements



• 203 NEW TREES


24 are required for mitigation.

179 are in addition to mitigation requirements!

• 2 MICRO-FORESTS


1,279 saplings!

Segment 9: Existing Trees vs. Proposed Trees



Segment 9: 349 Existing Trees Evaluated by a Certified Arborist








NEW PROPOSED TREES



TREES TO REMAIN OR RELOCATED

GUIDEWAY CLEARANCE AND TRAFFIC VIEW TRIANGLES



56% increase in number of trees

36
different species of trees, shrubs & groundcover

97% native species

Segment 9: New Planting Typical Composition





GROWS MUCH FASTER
THAN TRADITIONAL
AFFORESTATION
STRATEGIES



THE DENSITY ALLOWS
FOR SPECIES TO THRIVE
WITH VERY LOW
MAINTENANCE



PROVIDES VERY
HIGH BIODIVERSITY
IN A VERY LIMITED
FOOTPRINT



THE NATIVE PLANTINGS
PROVIDE REFUGE FOR
POLLINATORS, OTHER
ANIMALS AND FUNGI



PROVIDES ESSENTIAL ECOLOGICAL
SERVICES TO THE SURROUNDING
COMMUNITY AND
OPPORTUNITIES FOR LEARNING












Micro-forest: the first in South Florida! (Miyawaki afforestation method)

MICRO-FOREST VEGETATION LAYERS



Myrcianthes fragrans

Simpson's Stopper

Picramnia pentandra

Bitter Bush

3 GALLON POTS





Micro-forest: Composition

Chrysophyllum oliviforme

Satinleaf

Sideroxylon foetidissimum


False Mastic

Segment 5 Tree Management & Planting Strategy



Segment 5: from Le Jeune Rd. to SW 38th Ave. in the City of Coral Gables

EXISTING CONDITION 93 TREES



PROPOSED CONDITION

332 TREES (260% INCREASE)

68 TREES TO REMAIN

•68 TREES TO REMAIN

•23 TREES TO BE RELOCATED




•23 RELOCATED TREES

•3 TREES TO BE REMOVED

No specimen trees will be removed.

1 is dead, prohibited or in poor health.

2 are in conflict with design elements



• 241 NEW TREES

1 is required for mitigation per County regulations.

240 are in addition to mitigation requirements!

Segment 5: Existing Trees vs. Proposed Trees




Segment 5: 93 Existing Trees Evaluated by a Certified Arborist





TREES TO REMAIN OR RELOCATE

GUIDEWAY CLEARANCE AND TRAFFIC VIEW TRIANGLES



Segment 5: Plan overlay of existing trees over proposed design





NEW PROPOSED TREES



TREES TO REMAIN OR RELOCATED

GUIDEWAY CLEARANCE AND TRAFFIC VIEW TRIANGLES




260% increase in number of trees

33
different species of trees, shrubs & groundcover

94% native species

Segment 5: New Canopy Plan





Segment 5: New Planting Typical Composition




Segment 3 Tree Management & Planting Strategy



Segment 3: from SW 27th ave. to SW 19th ave. in the City of Miami

EXISTING CONDITION 288 TREES



PROPOSED CONDITION

480 TREES (67% INCREASE)

200 TREES TO REMAIN

200 TREES TO REMAIN

•31 TREES TO BE RELOCATED




•31 RELOCATED TREES

•57 TREES TO BE REMOVED

No specimen trees will be removed.

29 are dead, prohibited or in poor health.

28 are in conflict with design elements but mostly small and with poor ecological value.



• 249 **NEW TREES**

20 are required for mitigation per County regulations. 229 are in addition to mitigation requirements!

Segment 3: Existing Trees vs. Proposed Trees



Segment 3: 288 Existing Trees Evaluated by a Certified Arborist







TREES TO REMAIN OR RELOCATE

TREES TO REMOVE

GUIDEWAY CLEARANCE AND TRAFFIC VIEW TRIANGLES



Segment 3: Plan overlay of existing trees over proposed design






NEW PROPOSED TREES

TREES TO REMAIN OR RELOCATED

GUIDEWAY CLEARANCE AND TRAFFIC VIEW TRIANGLES



67% increase in number of trees


31
different species of trees, shrubs & groundcover

97% native species

Segment 3: New Canopy Plan







Segment 3: New Canopy Typical Composition



Segments 3, 5 and 9 will include 693 new trees and over 98,000 new understory plants!

Hello again...





Construction Talk

- O1 The Team
- 02 Schedule
- **Typical Construction Sequence & Activities**
- **Safety: MOT**
- **Tree Protection**
- 06 Communication

Who we are


















45+ Award-winning Builders for years in South Florida






The Design-Build Team

Phase 3 Groundbreaking Ceremony

University Metrorail Station / September 12, 2023

Let's talk about schedule




The Underline Phase 3: Project Schedule

What you can expect during construction



Typical Construction Sequence

- **Site Preparation**
- **Tree Protection & Trimming**
- **Safety Measures: MOT (Signs and Detours)**
- **Earthworks & Underground Infrastructure**
- **Pathways and Above Ground Infrastructure**
- 06 Intersections & Amenities
- 07 Landscaping



Typical Construction Sequence: SITE PREPARATION



Typical Construction Sequence: TREE PROTECTION




Typical Construction Sequence: SAFETY MEASURES - MOT



Typical Construction Sequence: UNDERGROUND INFRASTRUCTURE



Typical Construction Sequence: PATHWAYS & TRAILS



Typical Construction Sequence: LIGHTING & AMENITIES



Typical Construction Sequence: LANDSCAPING


Your safety is our top priority

MOT - Maintenance of Traffic





- FDOT Requirements and Guidelines
- Signed & Sealed Plans by Traffic Engineer
- Reviewed and Approved by FDOT / DTPW / (FoU)
- Timely 'Closure' Coordination and Notification to Public



The Underline Phase 3: Typical MOT Plan – SAFETY MEASURES

Building with green in mind



Today:

2,474 trees & palms

→ 68% to remain in place

→ 18% to be relocated

→ 13% to be removed

When Complete:

3,960 trees & palms

→ 1,800 new trees & palms

→ 62.5% increase



Tree Tagging, Protecting, Relocating



We are here



How to reach us.

The Underline

Miamidade.gov/TheUnderline

DEPARTMENT OF TRANSPORTATION AND PUBLIC WORKS

miamidade.gov/transportation f 📉 🔘 @GoMiamiDade









Thank you!