

Miami-Dade Water and Sewer Department

Emergency 60-Inch Force Main Installation

Fisher Island to Miami Beach

PROJECT DESCRIPTION:

The existing 54-inch sewer force main between Fisher Island and Miami Beach will be replaced with approximately 3,500 feet of new 60-inch force main. The overall installation, divided into four phases, started in Summer 2011 and is expected to be completed by Summer 2013.

PROJECT PHASES:

PHASE 1 Includes the pipeline portion beneath Government Cut between Fisher Island and a marine shaft located adjacent to the Miami Beach Marina. The line will be placed at 80 feet below sea surface with approximately 1,200 linear feet of new 60-inch force main installed via micro-tunnel trenchless technology. The relocated pipeline will allow future dredging of the Miami Harbor. Construction for Phase 1 started in August 2011, and is anticipated to be substantially complete by the end of 2012.

PHASE 2 Includes the installation of approximately 700 linear feet of micro-tunnel from the marine shaft to a new land shaft located in South Pointe Park. This phase also includes approximately 450 feet of open-cut pipeline installation in South Pointe Park terminating at the southern end of Washington Avenue. Construction for Phase 2 is anticipated to start in June 2012, and be completed by the end of June 2013.

PHASE 3 Includes the installation of approximately 1,025 linear feet of open-cut pipeline from the southern end of Washington Avenue, heading north along Washington, turning west on Commerce Street and terminating on Commerce Street just east of Jefferson Avenue. To minimize disruption to the neighborhood, this phase was procured as an emergency contract to be installed in Summer 2012, beginning in early August 2012 and completed by November 2012.

PHASE 4 Includes the installation of approximately 130 linear feet of open-cut pipeline installation along the west end of Commerce Street, crossing Jefferson Avenue and making the final tie-in connection into the existing 54-inch force main located along Alton Road. This work will be carried out in two parts, the first between September and November 2012, and the second between April and June 2013.

COMMUNITY MEETING:

Join us to get the latest information:

Date: Wednesday, June 27, 2012

Location: Pearl at Nikki Beach

1 Ocean Drive Miami Beach, FL 33139

Time: Meeting to begin at 6:30 p.m.,
presentation at 7 p.m.

Thanks to Nikki Beach for facilitating the meeting venue.



Delivering Excellence Every Day

Miami-Dade Water and Sewer Department Emergency 60-Inch Force Main Installation Fisher Island to Miami Beach

CONTACTS:

Adriana P. Lamar, Public Affairs Manager
Miami-Dade Water and Sewer Department
3071 SW 38 Avenue, Suite 539
Miami, FL 33146
Phone: (786) 552-8087
E-mail: alamar@miamidade.gov

Alicia Gonzalez, Public Information Manager
Media Relations Group, LLC
18001 Old Cutler Road, Suite 407
Palmetto Bay, FL 33157
Phone: (786) 280-6645
E-mail: agonzalez@mrgmiami.com

